Insured: Jane Smith Home: (800) 555-5550 x 1234
Property: 456 NE. Main Street Business: (800) 555-5551 x 5678

Lehi, UT 84043 Cell: (800) 555-5552

Home: 123 Eastern Way Pager: (800) 555-5553

Lehi, UT 84043 E-mail: testing1@testing.com

Claim Rep.: BRIAN

Claimant: Jim Jones Business: (800) 555-5554 x 987

Business: 345 West Street

Lehi, UT 84043

Estimator: Davey Jones Business: (555) 555-1234
Position: Adjuster E-mail: test@testing.com

Company: Xactware Business: 123 Drive

Lehi, UT 84043

Reference: Billy Business: (555) 555-9876

Position: Business Owner E-mail: billy.smith@testing.edi.org

Company: Billy Smith
Business: 1 Way Street

Provo, UT 84604

Contractor: Kyle Business: (555) 555-2468

Company: Kyle Doe Jr. E-mail: kyle@contractor.test.com

Business: Eastern Way

Lehi, UT 84043

Claim Number: GSD-1152018-11 Policy Number: DJT-123456-987 Type of Loss: Fire

Date Contacted: 1/28/2019 10:00 AM

Date of Loss: 11/4/2018 10:15 AM Date Received: 11/5/2018 10:42 AM Date Inspected: 1/31/2019 2:00 PM Date Entered: 2/1/2019 10:34 AM

Date Est. Completed: 2/1/2019 11:13 AM


Price List: UTOR8X_FEB19

Restoration/Service/Remodel

Estimate: JANE_SMITH

JANE_SMITH

Main Level



Family Room

 435.67 SF Walls
 272.94 SF Ceiling

 708.61 SF Walls & Ceiling
 272.94 SF Floor

30.33 SY Flooring 53.25 LF Floor Perimeter 60.50 LF Ceil. Perimeter

Missing Wall

5' 8" X 8'

Missing Wall - Goes to Floor

7' 3" X 6' 8"

Opens into FOYER_ENTRY Opens into KITCHEN

Height: 8'

DESCRIPTION	QUANTITY	UNIT PRICE	TAX	RCV	DEPREC.	ACV
R&R Carpet pad - Standard grade	272.94 SF	0.49	6.08	139.82	(0.00)	139.82
2. Remove Carpet - High grade	272.94 SF	0.22	0.00	60.05	(0.00)	60.05
3. Carpet - High grade	316.00 SF	4.60	86.81	1,540.41	(0.00)	1,540.41
4. R&R 1/2" drywall - hung, taped, with smooth wall finish	708.61 SF	2.67	24.87	1,916.86	(0.00)	1,916.86
5. Clean table - sofa - large/ornate - Heavy clean	1.00 EA	37.13	2.51	39.64	(0.00)	39.64
6. Seal & paint trim - two coats	53.25 LF	1.16	0.36	62.13	(0.00)	62.13
7. Clean trim - wood - Heavy	53.25 LF	0.40	0.04	21.34	(0.00)	21.34
Totals: Family Room			120.67	3,780.25	0.00	3,780.25

4' 10" - 5' - 5' 3" - 5' 1" - 5' 1" - 5' 1" - 6' 1 14' 11" - 5' 1" - 6' 1 14' 11'' - 6' 1 14' 11'' - 6' 1 14' 11'' - 6' 1 14' 11'' - 6' 114' 11'' - 6' 114' 11'' - 6' 114' 11'' - 6' 114'

Kitchen

Height: 8'

329.00 SF Walls130.29 SF Ceiling459.29 SF Walls & Ceiling130.29 SF Floor14.48 SY Flooring39.92 LF Floor Perimeter

47.17 LF Ceil. Perimeter

Opens into FAMILY_ROOM

Missing Wall - Goes to Floor 7' 3" X 6' 8"

DESCRIPTION	QUANTITY	UNIT PRICE	TAX	RCV	DEPREC.	ACV
8. R&R Tile floor covering	130.29 SF	11.55	35.27	1,540.12	(0.00)	1,540.12
9. R&R Tile base - Standard grade	39.92 LF	15.19	6.90	613.28	(0.00)	613.28
Totals: Kitchen			42.17	2.153.40	0.00	2.153.40

Total: Main Level 162.84 5,933.65 0.00 5,933.65

Labor Minimums Applied

DESCRIPTION	QUANTITY U	NIT PRICE	TAX	RCV	DEPREC.	ACV
10. Cleaning labor minimum	1.00 EA	30.08	0.00	30.08	(0.00)	30.08
11. Painting labor minimum	1.00 EA	123.61	0.00	123.61	(0.00)	123.61
Totals: Labor Minimums Applied			0.00	153.69	0.00	153.69
Line Item Totals: JANE_SMITH			162.84	6,087.34	0.00	6,087.34

Grand Total Areas:

1,061.22	SF Walls SF Floor SF Long Wall	117.91	SF Ceiling SY Flooring SF Short Wall	303.83	SF Walls and Ceiling LF Floor Perimeter LF Ceil. Perimeter
· /	Floor Area Exterior Wall Area	,	Total Area Exterior Perimeter of Walls	2,460.89	Interior Wall Area
	Surface Area Total Ridge Length		Number of Squares Total Hip Length	0.00	Total Perimeter Length

Coverage	Item Total	%	ACV Total	%
Structure	6,017.62	98.85%	6,017.62	98.85%
Contents	69.72	1.15%	69.72	1.15%
Total	6,087.34	100.00%	6,087.34	100.00%

Summary for Structure

Line Item Total	5,857.29
Material Sales Tax	160.33
Replacement Cost Value	\$6,017.62
Less Deductible	(500.00)
Net Claim	\$5,517.62
Davey Jones	_
Adjuster	

Summary for Contents

Line Item Total		67.21
Contents Cln Svc Tax		2.51
Replacement Cost Value		\$69.72
Less Deductible	[Full Deductible = 100.00]	(69.72)
Net Claim		\$0.00
	Davey Jones	_
	Adjuster	

Recap of Taxes

	Material Sales Tax (6.75%)	Manuf. Home Tax (6.75%)	Storage Rental Tax (6.75%)	Contents Cln Svc Tax (6.75%)	Food Tax (3%)
Line Items	160.33	0.00	0.00	2.51	0.00
Total	160.33	0.00	0.00	2.51	0.00

Recap by Room

Estimate: JANE_SMITH

Area: Main Level			
Family Room		3,659.58	61.77%
Coverage: Structure	98.99% =	3,622.45	
Coverage: Contents	1.01% =	37.13	
Kitchen		2,111.23	35.64%
Coverage: Structure	100.00% =	2,111.23	
Area Subtotal: Main Level		5,770.81	97.41%
Coverage: Structure	99.36% =	5,733.68	
Coverage: Contents	0.64% =	37.13	
Labor Minimums Applied		153.69	2.59%
Coverage: Structure	80.43% =	123.61	
Coverage: Contents	19.57% =	30.08	
Subtotal of Areas		5,924.50	100.00%
Coverage: Structure	98.87% =	5,857.29	
Coverage: Contents	1.13% =	67.21	
Total		5,924.50	100.00%

Recap by Category

Items			Total	%
CONT: CLEAN - HARD FURNITURE			37.13	0.61%
Coverage: Contents	@	100.00% =	37.13	
CLEANING			51.38	0.84%
Coverage: Structure	@	41.46% =	21.30	
Coverage: Contents	@	58.54% =	30.08	
GENERAL DEMOLITION			626.20	10.29%
Coverage: Structure	@	100.00% =	626.20	
DRYWALL			1,665.23	27.36%
Coverage: Structure	@	100.00% =	1,665.23	
FLOOR COVERING - CARPET			1,562.78	25.67%
Coverage: Structure	@	100.00% =	1,562.78	
FLOOR COVERING - CERAMIC TILE			1,796.40	29.51%
Coverage: Structure	@	100.00% =	1,796.40	
PAINTING			185.38	3.05%
Coverage: Structure	@	100.00% =	185.38	
Subtotal			5,924.50	97.32%
Material Sales Tax			160.33	2.63%
Coverage: Structure	@	100.00% =	160.33	
Contents Cln Svc Tax			2.51	0.04%
Coverage: Contents	@	100.00% =	2.51	
Total			6,087.34	100.00%